

METHOD · CONCEPT TO INSTALLATION

Installation & handling.

How an H&P project runs from specification to handover, and what the installing contractor needs to know on site.

STEP 01

Specification & shop drawings

We review drawings, finishes and site conditions, then issue shop drawings and material recommendations for sign-off before anything is cut.

STEP 02

Engineering review

Load, code and connection details are engineered so every panel and rail meets structural and compliance requirements for the jurisdiction.

STEP 03

Fabrication

Cutting, forming, welding and finishing in premium American steel, stainless, aluminium, copper, brass and corten — to tight, repeatable tolerances.

STEP 04

Delivery & installation support

Coordinated to your construction schedule, with installation guidance and documentation for the project record.

On site

- **Receiving** — inspect against the packing list on delivery and photograph any transit damage before signing. Report within 48 hours.
- **Handling** — lift panels on their long edge with clean gloves. Do not drag finished faces. Fresh Corten will mark porous surfaces it rests on.
- **Storage** — store off the ground, spaced and under cover with airflow. Trapped moisture between stacked panels causes uneven early patina.
- **Setting out** — work to the issued shop drawings, not to the architectural drawings, once shop drawings are signed off. Confirm datum and tolerances before fixing.
- **Fixings** — use the specified fixings only. Mixing metals at the fixing point invites galvanic corrosion; isolate dissimilar metals with the supplied washers.
- **Cutting on site** — avoid where possible. Any cut edge on Corten or stainless must be de-burred and cleaned; site cuts void finish warranty on coated products.

- **Handover** — retain shop drawings and this document in the project record.

Questions during installation: call fabrication on (720) 609-9307 or email sales@hnpbuilding.com quoting your project reference.